


o'neill plan has been moved and rotated
LOSE 1133
GAIN 1324
No. Bearing Distance
L1 N02°08'04"E 10.00'
trov
92,669 S.F.
2.1 Ac.
c6484lot1
91,238 S.F.
2.1 Ac.
d14247
180,254 S.F.
4.1 Ac.
perimabut
147,973 S.F.
3.4 Ac.
PROPOSED W.W.A. TANK
APPROX. AREA OF FILL/DISTURBANCE
323.74'
S69°41'00"W
471.27'
S69°49'15"W
327.60'
N59°50'41"W
309.25'
N67°16'32"W
313.10'
N81°43'26"E

Command= 210-

Point#, Start#-End# or G#= 1-264

Bearing	Distance	Elev	Descrip	Pnt.	Northing	Easting	Type
-------------------------12-19-2023-----10:49:35-----------D:\BENCH FILES\BMHOME							
				1	5005.4802	5001.4933	
				2	4966.0451	5146.2168	TRA
				3	4958.8632	5421.9133	TRA
				4	5007.4801	5410.2344	TRA
				5	5105.6524	5523.9369	TRA
				6	5234.3434	5236.5884	TRA
				7	5134.7517	5189.8820	TRA
				8	5198.4422	5054.0751	TRA
				9	5000.0000	5000.0000	TRA
				10	4901.3736	5050.3628	TRA
				11	4837.8818	5036.4419	TRA
				12	4853.9443	4963.1822	TRA
				13	4565.5917	4891.7733	TRA
				14	4568.6196	4977.0595	TRA
				15	4558.6259	4977.4144	TRA
				16	4560.6536	5034.5284	TRA
				17	4626.3158	5166.7074	TRA
				18	4738.7211	5470.3069	TRA
				19	4755.0172	5489.2979	TRA
				20	4642.6120	5185.6984	TRA
				21	4576.9498	5053.5194	TRA
				22	4578.9775	4996.4054	TRA
				23	4588.9712	4996.7602	TRA
				24	4591.9992	4911.4740	TRA
				25	4853.9443	4963.1822	TRA
				26	4837.8818	5036.4419	TRA
				27	4901.3736	5050.3628	TRA
				28	4917.4361	4977.1030	TRA
				29	5000.0000	5000.0000	TRA
				30	5000.0000	5000.0000	
				31	4959.9142	5144.5446	TRA
				32	4978.1345	5439.5324	TRA
				33	4746.0095	5495.2143	TRA
				34	4584.7291	5052.4005	TRA
				35	4587.1317	4987.9453	TRA
				36	4597.1247	4988.3177	TRA
				37	4600.3044	4903.0370	TRA
				38	4860.5958	4964.0212	TRA
				39	4922.9084	4978.6205	TRA

JOB #19 423FOWLER [264]

Bearing	Distance	Elev	Descrip	Pnt.	Northing	Easting	Type
------------------------		12-19-2023-----		10:49:35-----------		D:\BENCH FILES\BMHOME	
				40	4828.4359	5110.5331	TRA
				41	5192.7258	5053.4486	TRA
				42	5012.8577	5423.5856	TRA
				43	4958.2809	5444.2688	INT
				50	5109.3608	5529.1264	
				51	5026.7992	5427.8176	TRA
				52	4746.9441	5500.9296	TRA
				53	4585.1624	5539.8180	TRA
				54	4630.2311	5849.6574	TRA
				55	4531.7313	5859.5965	TRA
				56	4538.2983	5905.5598	TRA
				57	4864.7759	5857.4727	TRA
				58	4874.1109	5922.8092	TRA
				59	4951.2190	5911.4519	TRA
				60	5070.5161	5626.1384	TRA
				61	5109.3608	5529.1264	TRA
				62	4583.0474	5053.3970	TRA
				63	4745.1112	5495.9246	TRA
				64	4977.1356	5439.8254	TRA
		59.80	1SETMGNL	101	5198.1638	5045.0676	
		58.25	2FDDHSB	102	5000.0000	5000.0000	
		65.56	3SETHUB	103	5005.9797	5183.4287	
		64.13	4SETHUB	104	4976.7131	5274.3217	
		62.44	5SETHUB	105	5049.9148	5362.1538	
		61.29	6SETMGNL	106	5157.7701	5441.0081	
		410.21	7SETMGNL	107	5322.3395	5157.7399	
		62.33	corgar	108	5094.8674	5119.5860	SS
		60.87	toptank	109	5110.7138	5102.8944	SS
		61.11	corpav	110	5113.1735	5081.1436	SS
		61.38	corgar	111	5104.3136	5079.3627	SS
		60.22	ep	112	5115.7377	5066.1116	SS
		58.57	corep	113	5116.1210	5033.1068	SS
		61.67	bmfndnl*	114	5127.9169	5042.3348	SS
		59.48	bksdwk5	115	5140.1484	5038.8276	SS
		59.68	bksdwk5	116	5169.7556	5043.7217	SS
		58.78	setnlpin	117	5192.8201	5053.1870	SS
		59.92	endtrln	118	5163.7615	5085.7130	SS
		61.68	pine	119	5140.1547	5122.4608	SS
		61.85	r1pine	120	5143.7341	5135.7578	SS
		62.08	r1.5end*	121	5153.4139	5133.4437	SS
		59.13	gnd	122	5152.8642	5062.1120	SS
		60.41	gnd	123	5135.0804	5088.9410	SS
		58.96	gnd	124	5188.9274	5061.6715	SS
		60.22	24map	125	5208.3472	5071.8467	SS
		61.49	36map	126	5196.4105	5099.8796	SS
		59.67	pole***	127	5275.5637	5044.9946	SS
		58.92	cbasin**	128	5303.3906	5057.1655	SS
		59.21	epcrb**	129	5222.0411	5039.4905	SS
		59.08	epcrb**	130	5185.8493	5035.7870	SS
		58.36	cbasin**	131	5133.8609	5028.2329	SS
		58.67	whlnepdr	132	5118.4428	5019.0149	SS
		58.66	whlnepdr	133	5105.7167	5016.3323	SS
		60.16	lilac	134	5126.7464	5075.2414	SS
		60.59	epdrpt	135	5094.7491	5065.7369	SS
		60.15	epdrpc	136	5090.0151	5056.0024	SS
		60.20	epdr**	137	5074.5547	5052.4622	SS
		60.14	epdr	138	5057.3617	5048.3377	SS
		59.71	epdrpt	139	5081.4319	5043.6864	SS

JOB #19 423FOWLER [264]


Bearing	Distance	Elev	Descrip	Pnt.	Northing	Easting	Type
-------------------------		12-19-2023-----		10:49:35-----------		D:\BENCH FILES\BMHOME	
		59.27	epdroc	140	5095.4826	5038.8371	SS
		58.60	epdr**	141	5103.8853	5025.4885	SS
		59.81	map*	142	5092.1485	5032.6499	SS
		60.15	map*	143	5068.4887	5033.8426	SS
		59.30	sign	144	5069.5026	5025.7718	SS
		58.94	sign**	145	5071.0862	5019.1682	SS
		59.93	maple*	146	5051.5823	5023.7741	SS
		58.42	low**	147	5069.6078	5013.0213	SS
		57.91	pole	148	5030.0665	4965.5880	SS
		58.19	mailbox	149	5103.6773	4987.1975	SS
		57.23	pole**	150	5138.0425	4992.5484	SS
		56.47	topculv*	151	5141.1810	4993.6673	SS
		53.23	hw??	152	5184.4384	4927.6370	SS
		52.86	hw??	153	5145.0991	4922.9050	SS
		53.08	edgwet	154	5187.0980	4944.7662	SS
		53.43	edgwet**	155	5112.5776	4935.8333	SS
		62.41	edglwn	156	5157.0710	5191.7088	SS
		62.41	shed	157	5199.7345	5186.5689	SS
		62.66	shed	158	5208.7892	5190.7306	SS
		64.83	topwell*	159	5204.2693	5180.9105	SS
		63.00	corhse	160	5215.4791	5154.2228	SS
		62.58	corhse	161	5233.2185	5117.4121	SS
		60.00	bksign**	162	5278.6102	5065.2932	SS
		61.63	garslab	163	5097.2640	5078.0059	SS
		58.50	scrvsgn	164	5013.0851	5001.1997	SS
		58.70	eddredsh	165	5038.4718	5010.6548	SS
		58.73	ep**	166	5040.3529	5002.4952	SS
		58.53	low**	167	5023.3373	5001.5692	SS
		58.94	epdr	168	5024.0668	5013.8551	SS
		59.95	12map**	169	5010.2017	5014.2435	SS
		60.20	apple	170	5003.5335	5032.2470	SS
		61.62	maple	171	4993.6964	5063.8797	SS
		62.06	corhse	172	5017.4325	5061.5177	SS
		61.84	corhse	173	5025.7213	5061.3243	SS
		61.92	corhse	174	5067.1824	5070.9491	SS
		61.87	corhse	175	5072.6392	5072.1046	SS
		62.74	up.65fl	176	5070.8023	5071.8175	SS
		62.39	flel	177	5082.0161	5074.3048	SS
		64.36	thresh	178	5040.4336	5064.7410	SS
		60.11	epdr	179	5034.3042	5042.3237	SS
		59.91	epdr	180	5026.6564	5036.8369	SS
		59.55	epdr	181	5022.7731	5028.4475	SS
		59.96	epdr	182	5053.9658	5037.3671	SS
		59.59	epdr	183	5040.7444	5026.0497	SS
		59.63	epdrpc*	184	4987.4954	4997.8389	SS
		60.98	corshed	185	4914.3245	5071.4361	SS
		60.41	corshed	186	4916.4409	5061.5312	SS
		60.17	corlib	187	4914.3461	5041.4588	SS
		61.97	corlibpr	188	4918.8463	5021.6425	SS
		59.60	corprch	189	4924.3931	5016.3283	SS
		58.42	pole	190	4859.9070	4966.5977	SS
		60.34	topwl1.2	191	4929.3325	4995.0590	SS
		58.03	lowwet	192	4953.5906	4988.0629	SS
		58.55	ep**	193	4955.4285	4981.0057	SS
		60.31	eplib**	194	4974.5968	5052.4300	SS
		52.64	hw?**	195	5086.0480	4930.9620	SS
		57.00	bmusgs	196	4911.3539	4859.4617	SS
		52.94	water***	197	4907.1505	4856.6774	SS

JOB #19 423FOWLER [264]

-------------------------12-19-2023-----10:49:35-----------D:\BENCH FILES\BMHOME


Bearing	Distance	Elev	Descrip	Pnt.	Northing	Easting	Type
		63.14	fddhsb	198	4828.4299	5110.5369	SS
		64.65	fddhsb*	199	4960.0129	5144.4939	SS
		64.01	fcpost**	200	4971.4112	5136.2843	SS
		61.67	fcpost**	201	4983.2119	5081.5416	SS
		62.25	corhse	202	5014.2471	5075.2842	SS
		62.46	corhse	203	5019.8367	5086.9790	SS
		62.79	corhse	204	5061.1448	5096.4352	SS
		62.60	corgar	205	5063.3411	5112.3595	SS
		62.39	corgar	206	5094.8821	5119.5706	SS
		62.49	clmpb**	207	5104.2367	5153.4108	SS
		63.46	edgwds	208	5087.0771	5187.5085	SS
		62.65	setspk**	209	5134.2677	5191.3112	SS
		64.69	coredwds	210	5075.7204	5218.5609	SS
		66.03	bldr**	211	5061.3995	5193.2306	SS
		64.32	12brch	212	5070.1613	5194.0836	SS
		64.98	dbpine**	213	5072.5825	5184.4032	SS
		64.82	corarea	214	5015.2585	5161.8599	SS
		63.67	tree	215	4997.2964	5134.2494	SS
		64.00	ts	216	5021.5958	5134.4583	SS
		62.49	bs	217	5036.8598	5119.1073	SS
		62.79	censand*	218	5051.2665	5142.9959	SS
		65.00	backbld*	219	5037.2983	5217.5697	SS
		66.87	topwell*	220	5025.0751	5238.1845	SS
		65.17	@fnc**	221	4960.3646	5172.3551	SS
		64.56	@corfnc*	222	4960.5876	5233.3733	SS
		63.50	setdh**	223	5021.1406	5429.4938	SS
		63.12	gnd**	224	5010.1146	5316.2290	SS
		64.71	setdh**	225	4969.2313	5441.6949	SS
		60.93	fndipin	226	5109.3608	5529.1264	SS
		62.62	setspk**	227	5236.3956	5232.8504	SS
		61.93	app<iron	228	5240.6505	5230.3279	SS
		61.93	appip**	229	5235.4900	5237.0300	SS
		62.73	corgar	230	5227.9386	5213.6001	SS
		61.52	endwll	231	5200.1723	5308.8153	SS
		71.21	concbnd*	232	4951.1860	5911.5289	SS
			disk	233	4926.7858	5039.5855	INT
			int/pob	234	5185.2198	5082.6655	INT
			calcor	235	5197.9578	5055.5041	TRA
			calcor	236	5233.8596	5238.0173	TRA


Point#, Start#-End# or G#= 4-



EXISTING CONDITIONS SITE PLAN
VILLAGE CHILDREN'S CENTER OF AUBURN
AUBURN, NH
SCALE:1"=20' AUGUST 9, 2004
STOCKTON SERVICES
PO BOX 1306, HAMPTON, NH 03843-1306
603 474-1954
GRAPHIC SCALE
(IN FEET)
1 inch = 20 ft.
LEGEND
FND IP FOUND IRON PIPE
SET DH SET DRILL HOLE
FND IPIN FOUND IRON PIN (REBAR)
FND SB FOUND STONE BOUND
STONE WALL
WIRE FENCE
UTILITY POLE
CATCH BASIN
OHW OVERHEAD WIRES
EOP EDGE OF PAVEMENT
DRAIN LINE
WATER LINE
EXISTING WELL
NOTES
1. OWNER OF RECORD: RICHARD G. & ANN L. OWEN RCRD 2472-0568
APPLICANT: AUBURN VILLAGE CHILDREN'S CENTER GREGORY & MARJORIE FOWLER
LOCUS: 32 HOOKSETT ROAD AUBURN, NH 03032 TAX MAP 26 LOT 10-1
2. CONDITIONAL APPROVAL GRANTED BY THE AUBURN PLANNING BOARD SEPT 17, 2003
1. EXPAND OPERATIONS TO 12 MONTHS A YEAR.
2. EXTEND OPERATING HOURS TO 6 AM TO 6 PM.
3. INCREASE ENROLLMENT TO 45 STUDENTS.
4. ADD 2 ADDITIONAL EMPLOYEES.
3. SUBJECT PROPERTY IN NOT LOCATED IN A FEDERALLY DESIGNATED FLOOD HAZARD ZONE. REFERENCE FEMA FIRM COMMUNITY 330176A PANELS 1 AND 2, DATED APRIL 2, 1986.
4. TOPOGRAPHIC DATUM IS GLOBAL ADJUSTMENT OF MINUS 200' FROM APPROX USGS.
STANDARD URBAN PROPERTY SURVEY
I CERTIFY THAT THIS SURVEY PLAT IS NOT A SUBDIVISION PURSUANT TO THIS TITLE AND THAT THE LINES OF STREETS AND WAYS SHOWN ARE THOSE OF PUBLIC OR PRIVATE STREETS OR WAYS ALREADY ESTABLISHED AND THAT NO NEW WAYS ARE SHOWN.
ANNE W. BIALOBRZESKI LLS #752 DATE 8/9/04
STATE OF NEW HAMPSHIRE ANNE W. BIALOBRZESKI No. 752 LICENSED LAND SURVEYOR
LOCATION PLAN
NOT TO SCALE
LOCUS
HOOKSETT ROAD
EATON ROAD
RAYMOND ROAD
ROUTE 121
CHESTER ROAD
EATON ROAD (A/K/A EATON HILL ROAD)
S64°33'14"E 78.40'
S67°35'55"E 238.29'
(DEED:150') 133.08' S48°28'36"W
S13°13'37"E 53.32' (DEED:50')
297.34' S88°13'24"W
N74°31'52"W 149.92'
N15°39'45"E 205.59' (PLAN:200)
S64°52'29"E 30.00'
S64°52'29"E 120.00'
N25°07'31"E 110.00'
EXISTING HOUSE
GARAGE
SHED
EXISTING WELL
N/F PATRICIA J. REYNOLDS & CONRAD L. CLEMENT RCRD 2886 2656 TAX MAP 26 LOT 8
PROTECTIVE RADIUS FOR WELL
SET SPIKE FND WOOD STAKE
SUCKER BROOK
APPROX HIGH WATER
HOOKSETT ROAD
EXISTING CURB
SIDEWALK
EXIS PAVED
CATCH BASIN RIM EL 58.36
INV EL 54.7
15" RCP
134'±
125'
* SHORELAND PROTECTION ACT CALLS FOR 125' SEPTIC SYSTEM SETBACK WITH SANDY SOILS OTHER USES ARE REGULATED WITHIN 250' OF SHORELINE
BM#1 FND NAIL 15" MAPLE EL 61.67
EXISTING 20X30 LEACH FIELD
262' TO USGS DISK AT LIBRARY
UNCUT LOW GROWTH
WOODS
GRASS
LILAC
EXIS SEPTIC TANK
UNCUT LOW GROWTH
PROPANE TANKS
EXISTING PARKING 2 CARS
EXISTING PARKING 2 CARS
EXISTING BUILDING
SLAB EL 61.63
FLOOR EL 62.39
FLOOR EL 63.39
DAY CARE CENTER
FLOOR EL 64.35
RAMP
DRIVEWAY
8'± WIDE GRAVEL SHOULDER
SIGN
MAILBOX
MAPLE
APPLE
PINE
BIRCH
BOULDER
APPROX WATER LINE
APPROX PLAYGROUND AREA 15,000 SF±
APPROX SUMP OUTFALL
EXISTING PARKING 2 CARS
LOT AREA 2.13 ACRES± 92,950 SF±
RCRD 2472-0568
RCRD PLAN C6484
TAX MAP 26 LOT 10-1
FND IPIN
SET DH
(NO DRILL HOLES FND)
RCRD PLAN C14627
RCRD PLAN C6484
N/F JACK SAMOWITZ & SHEILA KLEIN RCRD 2858-0594 RCRD PLAN D14247 TAX MAP 26 LOT 3-1
N/F MICHAEL J, JR & LAURIE A. NORTON RCRD 3765-2137 RCRD PLAN C14627 TAX MAP 26 LOT 10
N/F TOWN OF AUBURN RCRD 538-012 RCRD 2612-2349 RCRD PLAN D27977 RCRD PLAN C14627 TAX MAP 26 LOT 9
LIBRARY PARKING LOT
125' PROTECTIVE RADIUS AS SHOWN ON RCRD PLAN D27977
EXISTING WELL
REFERENCE RCRD 2947-1363
FND SB
APPROX C6484

LOCUS MAP

NOT TO SCALE







ALL SPECIFICATIONS AND RESPONSIBILITIES OUTLINED IN THE CLEAN SOLUTION MANUAL ARE A PART OF THIS DESIGN. MAINTENANCE CONTRACT MUST BE EXECUTED PRIOR TO INSTALLATION.

WASTEWATER ALTERNATIVES, INC.
TECHNOLOGY DEVELOPED BY:
HAROLD DAVIS
37 CHAMPNEY STREET
GROTON, MA 01450
978 448-2415

CROSS SECTION DISPOSAL SYSTEM – NOT TO SCALE

SOIL CLASS: 42B CANTON

(SOURCE: USDA-SCS SOIL SURVEY)

BENCH MARKS: DATUM = ASSUMED

#1 FND NAIL 15" MAPLE ELEV 61.67

#2 CATCH BASIN RIM EL 58.36

#3 COR BLDG, SLAB ELEV 61.63

DESIGN INTENT:

1. THE BOTTOM OF THE EFFLUENT DISPOSAL SYSTEM SHALL BE CONSTRUCTED AT ELEVATION 59.24 WHICH IS APPROX 27" BELOW ORIGINAL GROUND ON THE HIGH CONTOUR OF DESIGNED EDS. EL 61.5±

SUITABLE REPLACEMENT AREA:


SYSTEM MUST BE REBUILT IN PLACE OR REDESIGNED.

LEGEND:

50	EXISTING CONTOUR
(50)	PROPOSED CONTOUR
50.0	EXISTING SPOT ELEVATION
(50.0)	PROPOSED SPOT ELEVATION


NOTES:

1. THIS PLAN IS NOT TO BE CONSTRUED AS A BOUNDARY SURVEY. PROPERTY LINES SHOWN ARE APPROXIMATED BASED ON INFORMATION FROM THE FOLLOWING SOURCE: RCRD 2472-0568, RCRD PLAN C6484
2. NHDES-WS&PCD SUBDIVISION APPROVAL NUMBER: #10692 PREVIOUS CONSTRUCTION APPVL #56406
3. THIS SYSTEM IS NOT DESIGNED TO HANDLE GARBAGE DISPOSAL WASTE.
4. NO SURFACE WATER OR WELL WITHIN 100' OF PROPOSED SYSTEM.
5. EXIS LEACH FIELD LOCATION BASED ON BEST AVAILABLE EVIDENCE. REMOVE ALL COMPONENTS AND ASSOCIATED ORGANIC MATERIAL WITHIN 5' OF PROPOSED DISPERSAL FIELD.
6. PROPOSED SYSTEM TO BE INSTALLED ONLY IN EVENT OF FAILURE OF EXISTING SYSTEM.



PLOT PLAN
1"=APPROX 100'

PLAN : 1"=20'



SYSTEM OWNER IS RESPONSIBLE FOR THE FOLLOWING OPERATING REQUIREMENTS

ENV-WS 1023.01 (a) SEPTIC TANKS SHALL BE INSPECTED FOR ACCUMULATION OF SLUDGE AND SURFACE SCUM AT LEAST ONCE EVERY YEAR.
(b) WHEN THE COMBINED THICKNESS OF SLUDGE AND SURFACE SCUM EQUAL 1/3 OR MORE OF THE TANK DEPTH, THE TANK SHALL BE PUMPED BY A LICENSED SEPTIC TANK PUMPER.

ENV-WS 1023.02 TO PREVENT OBSTRUCTION OF THE DISTRIBUTION LINES AND LEACH FIELD, GREASE AND BULKY WASTE SHALL NOT BE FLUSHED OR OTHERWISE INTRODUCED INTO THE SEPTIC SYSTEM.

ENV-WS 1023.03 TOXIC AND HAZARDOUS MATERIALS SHALL NOT BE FLUSHED OR OTHERWISE INTRODUCED INTO THE SEPTIC SYSTEM.

ENV-WS 1023.04 TO PREVENT DAMAGE TO THE DISTRIBUTION LINES AND LEACH FIELD, VEHICLES, LIVESTOCK, AND OTHER HEAVY OBJECTS SHALL NOT BE ALLOWED ON THE LEACH FIELD.

ENV-WS 1023.05 IF WET AREAS APPEAR ON THE GROUND SURFACE ABOVE THE DISTRIBUTION LINES OR LEACH FIELD OR IF DISAGREEABLE ODORS OCCUR, THE SYSTEM SHALL BE INSPECTED FOR THE SOURCE OF THESE PROBLEMS, AND CORRECTIVE ACTION SHALL BE TAKEN.

TEST PIT DATA

TEST PITS BY OTHERS. PIT #1 TAKEN FROM PRELIMINARY SEPTIC DESIGN BY P. KASPRZYK DATED 3-17-2004.
PIT #2 TAKEN FROM ORIGINAL SEPTIC DESIGN (APPROVAL #56406)

TEST PIT #1

TOWN INSPECTOR: CARRIE ROULEAU-COTE

DEPTH	COLOR	TEXTURE	STRUCTURE	CONSISTENCE
0 – 14"	10YR4/3	LOAMY	GRANULAR	LOOSE
14–25"	10YR7/8	LOAMY/SAND	SINGLE GRAIN	LOOSE
25–40"	2.5Y6/8	LOAMY/SAND	SINGLE GRAIN	LOOSE
40–56"	2.5Y6/3	SANDY/CLAY	GRANULAR	LOOSE
56–108"	2.5Y6/4	CLAYEY	MASSIVE	FIRM

PERC TEST: 3 MIN/INCH
ESTIMATED SEASONAL HIGH WATER TABLE IS AT 54" BELOW ORIG. GRADE
ROOTS WERE OBSERVED TO 36" BELOW GRADE
NO LEDGE OBSERVED

TEST PIT #2 EL 61.5±

0 –6" LOAM
6"–10' SAND AND SMALL STONES

PERK TEST: 11.0 MIN/IN (SIC)
SEASONAL WATER TABLE: 7.0'
HIGH WATER TABLE: 6.0'
NO LEDGE TO 10'

PERC TEST DATA

1976 11.0 MIN/IN(SIC) 2' DEPTH
2004 3 MIN/IN NO DEPTH REPORTED
(BY OTHERS)

DESIGN LOADING:
EXISTING DAY CARE CENTER
6 EMPLOYEES @ 35GPD = 210 GPD
45 CHILDREN @ 10 GPD = 450 GPD
TOTAL DESIGN LOADING = 660 GPD

AREA REQUIRED: PER CLEAN SOLUTION SPECIFICATIONS: 100 SF DISPERSAL FIELD REQUIRED.

AREA PROPOSED: 223 SQ FT DISPERSAL AREA PROVIDED

PROPOSED BACKUP REPLACEMENT (SEE NOTE 6)

SEPTIC SYSTEM PLAN

LOCUS: VILLAGE CHILDREN'S CENTER OF AUBURN
32 HOOKSETT ROAD
AUBURN, NH

OWNER: ANN L. OWEN
C/O VILLAGE CHILDREN'S CENTER OF AUBURN
32 HOOKSETT ROAD
AUBURN, NH 03032

NEW HAMPSHIRE Designer of Subsurface Disposal Systems
Ann W. Bialobrzeski No. 348
Water Supply & Pollution Control

APPLICANT:
STOCKTON SERVICES
PO BOX 1306
HAMPTON, NH 03842

DATE: APRIL 7, 2005

APPROVAL:

NEVER SUBMITTED

~~D 23068~~ D 27977 Hooksett Rd
C 6484
C 14627

~~2472-568~~
↑
Richard G & Ann L Owen
↑
(1) 2472-568 11/28/83
R 12/12/83
↑
(Lawrence A &) Helen J. Hurley
↑
11/5/76
R 11/29/76
2271-427 Lot 1 2.0 AC

Easement
2947-136
(1)

David & Kathleen Holman
↑
11/13/75
2247-1094 (1)

10/3/51
1225-101

Roy D & Henrietta S. Hand → Chas G & M Pauline Hand

~~1030-4~~

↑ 6/22/1945 1030-421

Dorothy D. Farwell

D 28941

Robt L & Denise M Holmes

↑ 2433-334 (1)

Katheen McKenzie (f. Kathleen Holman)

↑ 2437-1879 Lot 2 C6484

3/15/83
R 3/17/83

Mark May Esq
Divorce Lawyer

D 27977
C 6484

2433-334 (1)
2947-1366 (1)
2472-568 (1)
2247-1094 (1)

SEE CONDITIONS BELOW.

APPROVAL FOR CONSTRUCTION

APPROVAL NO. 56406

The plans and specifications for sewage or waste disposal system submitted for

LAWRENCE AND HELEN HURLEY, LOT #1, SUB. APPVL. #10692, TWO BEDROOM HOUSE LOCATED IN AUBURN, NH.

by

Walter O'Neill
293 Young St.
Manchester, NH 03103

are hereby approved.

Date: September 2, 1976

By: Louis E. Lavallee (bl)
N.H. Water Supply & Pollution Control Commission Staff

Copy of approval sent to:

Board of Selectmen
Town Office
Auburn, NH 03032

PLEASE POST IN A CONSPICUOUS PLACE DURING CONSTRUCTION - LOCAL APPROVAL MAY ALSO BE REQUIRED.

(over)

APPROVAL FOR OPERATION

NEW HAMPSHIRE WATER SUPPLY AND POLLUTION CONTROL COMMISSION
P.O. Box 95 - 105 Loudon Road
Concord, N. H. 03301

APPROVAL NO. 56406

The individual sewage or waste disposal system constructed for Lawrence & Helen Hurley, Manchester NH (name and address)

for Lot #1 [illegible] SD, Auburn NH

(describe property and location)

was inspected on [illegible] (date) before covering and is hereby approved for use.

Copy sent to:

Date approved: [illegible]

By: [illegible]

Authorized Agent of the New Hampshire Water Supply and Pollution Control Commission

THIS APPROVAL DOES NOT SUPERCEDE LOCAL ORDINANCES OR REGULATIONS.

(OVER)

Viera Artesian Well Company

JAMES F. VIERA

253 Andover Street
Georgetown, Massachusetts 01833
(508) 352-8588

Mr. Greg Fowler
81 Lyford Lane
Brentwood,NH 03833

603-231-7460

RE: former/ OWENS property 32 Hooksett Rd. , Auburn,NH

Viera Artesian Well Company, drilled a well at the above location for Ann Owen,


well depth was completed @ 405 ft.,setting 80ft., of 6"diam.well casing.


Well tested @ 20 GPM flow rate and was completed on 8-31-1998.


Our records indicate Smith Pump.Co., from Hooksett,NH provided pumping equipment/and or water analysis testing.


regards,
VIERA WELL CO.


cc: Village Childrens Center
32 Hooksett Rd. Auburn,NH 03032



KLEIN SHEILA
26-3-1
SAMOWITZ JACK
439 SKYTOP DRIVE
Fairfield CT
06825
2858-0594
11/9/90 transfer of title to leased property
2858-242
Postal Realty Trust
11/19/1990
Lot 26-3-1 Plan 14247
Patricia Reynolds
EATON
Library
26-9
0.484 Ac
NORTON
MICHAEL + LAURIE
26-10
3.2 Ac
GRIFFIN MILL ROAD
26-3
2.00 Ac
SHT 7
26-11
26-4
26-5
RAYMOND
26-16
26-17
0.58 Ac
26-18
0.40 Ac
ROUTE 121
MANCHESTER ROAD
CHESTER ROAD
26-20
26-21
26-1
26-2
2 Ac
SHT
SHT 10
26-3-1
OWITZ, JACK
N, SHELIA
14247
P.O.
ROAD
26-7
3.771 Ac
26-6
26-12
26-13
0.872 Ac
26-14
26-15
26-19
.883 Ac
SHT 7
26-22
12 Ac
26-23
26-24
26-25
26-26
26-27
26-28
7.25 Ac
ROUTE
121
GRAPHIC SCALE
PROPERTY MAP
AUBURN
NEW HAMPSHIRE
POLLARD ASSOCIATES
26












Direction from Route 101: Take exit 2 (Hooksett Road) follow South 1.2 miles. Subject parcel is on the left, Village Children's Center of Auburn.



CONSTRUCTION NOTES :

1.) Septic Tank; Precast concrete, AASHTO rating of H-20 or better. Distributed by A.J Foss concrete of Farmington, NH.
Tank to be sealed and grouted watertight and pump chamber shall be vented with 2" vent pipe, opening shall be covered with a wire mesh to prevent any foreign objects from entering the pipe. Vent opening to be 3' above grade.
2.) D-Box ; 5 outlet Precast Concrete, Distributed by A.J Foss of Farmington, NH
3.) Sewer pipe from building to septic tank shall be 4" solid SDR 26 (or equal) solvent welded plastic pipe with a minimum pitch of 1/4" (2 %) per foot. Pump discharge pipe shall be 1.5" Plastic 100 psi minimum pressure rated plastic pipe. Install elbow at end of sewer line where it enters tank 2 and the D-Box to reduce velocity of flow. Pump line to be installed below frost penetration (or insulated) and backfilled with clean sand free of stones. Sewer line (1.5") from tank 1 to tank 2 should be laid at such a pitch to allow back flow within the line from tank 2 to tank 1.
4.) All connections to be sealed with "waterplug cement".
5.) In accordance with state regulations, in the event of failure the system is to be re-built in place or in a suitable replacement site.
6.) All Enviro-Flo lines to be laid level.
7.) Baffles to be installed in compartment tanks as shown by A.J Foss concrete.
8.) A minimum of 6" of loam to used as a finish grade layer, planted with a perennial grass mix to prevent erosion. Do not plant or allow the growth of deep rooted vegetation on or near leachbed, tank or sewer line. Keep leachbed clear of heavy vegetation.
9.) Differential venting requires the high vent opening to be 10' above the lower, and should be supported by a 4X4 post. All vent openings to be covered with a heavy wire mesh to prevent any foreign objects from entering the pipes.
10.) Garbarge Disposal systems may cause premature system failure and are not recommended.
11.) Maintenance should include pumping tank one every six months and tank two Bi-annualy.
12.) Install Myers ME3H pump (set on a 4" block) and installed per manufacturers recommendations. Martinson Quick Disconnect model NGRD8 for pump removal. Available at Water Industries Inc. Alton, NH. Float alarm to be installed in pump chamber and set at elevations specified. Audubie/Visual alarm to be installed in prominant location in/on building. Seperate electronic circuits shall be provided for pump and alarm.
13.) Zabel filter to be cleaned and checked every 6 months when tank 1 is pumped or as needed for proper filtration of solids.

GENERAL NOTES:

1.) The subsurface disposal system has been designed in accordance with the rules, regulations and practices of the N.H Water Supply & Pollution Control as of of date of issue of the "Approval for Construction" (valid for 4 years). Construction must be done in strict accordance with this plan and those rules and regulations. Any changes or deviations from this plan may require revised or amended plans. Prior to backfilling or covering any componants the contractor must notify the state inspector for inspection of the system. In the event of system failure the system shall be repaired in place.
2.) This plan does not conform to local regulations. A variance was obtained through the planning board for installation as shown.
3.) This is a site plan and NOT a formal survey. The designer is not a licensed Land Surveyor and assumes no responsibility for boundary line delineation. Prior to installation a Licensed Land Surveyor should be consulted as to the location of boundary lines.

PUMP SPECIFICATIONS : Myers ME3H

DOSE VOLUME & SERVICE LINE SPEC'S:

Loading Volume = 750.0 gpd... -:- 8 doses minimum/day = 93.75
Service Line Legnth = 30.00 Feet Actual number of Doses/day = 8
Service Line Diameter = 1.5 inches Pump Chamber gals/inch = 6.2 gpi
Pump Switch / Off to On = 15.0 inches
Actual Pump Dose = 93.0 gals

TOTAL DYNAMIC HEAD (TDH) 11.06 Feet

D-Box Elevation = 102.44 feet Pump on Block, Block Height = 4.00 inch
Alarm on Elevation = 97.37'
Pump on Elevation = 96.87' Static Head = 6.82'
Pump Off Elevation = 95.62' Delivery Loss = 4.24'
Bottom of Tank Elevation = 94.12 feet Total Dynamic Head (TDH) = 11.06'

PUMP CAPACITY (gpm): (w/DBL FLOAT SWITCH AND ALARM)

Discharge Rate = 30 gpm Myers ME Delivers = 30 gpm
Pump Running Time = 3.1 mins

Drill 3/8" hole in checkvalve flapper to backdrain

SOILS DATA TEST PIT #1

CANTON GRAVELLY FINE SANDY LOAM 3-8% SLOPE
ROCKINGHAM COUNTY SOIL SURVEY DATA : 42B

DEPTH	COLOR	TEXTURE	STRUCTURE	CONSISTENCE
0 - 14"	10YR 4/3	Loamy	Granular	Loose
14" - 25"	10YR 7/8	Loamy / Sand	Single Grain	Loose
25" - 40"	2.5Y 6/8	Loamy / Sand	Single Grain	Loose
40" - 56"	2.5Y 6/3	Sandy / Clay	Granular	Loose
56" - 108"	2.5Y 6/4	Clayey	Massive	Firm

Perc Test: 3 Min / inch

Estimated Seasonal High Water Table is at 54" Below Original Grade

Roots were observed to 36" Below Grade

No Ledge observed

CALCULATIONS : SYSTEM CAPACITY 750 GPD

Required Spacing between Enviro-Flo pipes: 0-10% slope with a 1-10 min/in perc rate is 1.5' center to center.


Linear Footage Requirement: 750 GPD \ 100 * 47 = 352.5 Linear feet of Enviro-Flo pipe Based on information provided in the "

352 ft. / 10 ft. = 36 legnths of enviro-flo pipe required.

DESIGN INTENT

THE BED BOTTOM IS TO BE A MINIMUM OF 48" ABOVE THE ESTIMATED SEASONAL HIGH WATER TABLE (SHWT).

ME3H SERIES CURVE



Magnetic North 2003

SCALE : 1" = 20'

Prepared For :

Village Children's Center of Auburn
32 Hooksett Road
Auburn, N.H. 03032


NEW HAMPSHIRE Designer of Subsurface Disposal Systems PETER M. KASPRZYK No. 1062


Plan By :

Peter Kasprzyk
2344 Wakefield road
Wakefield, NH 03872

Scale 1" = 20'	Date 3-17-2004	Dwg No. 001-04

SEPTIC DESIGN: THIS PLAN SHOULD NOT BE USED TO DETERMINE BOUNDARIES, BEFORE LEACH FIELD IS INSTALLED IT IS RECOMMENDED THAT ALL BOUNDARIES BE LOCATED BY A PROFESSIONAL LAND SURVEYOR.





CONSTRUCTION NOTES

1.) Septic Tank; Precast concrete, AASHTO rating of H
Tank to be sealed and grouted watertight and pump cha
any foreign objects from entering the pipe. Vent opening
2.) D-Box ; 5 outlet Precast Concrete, Distributed by A.J
3.) Sewer pipe from building to septic tank shall be 4" sc
foot. Pump discharge pipe shall be 1.5" Plastic 100 psi m
and the D-Box to reduce velocity of flow. Pump line to b
stones. Sewer line (1.5") from tank 1 to tank 2 should be
4.) All connections to be sealed with "waterplug cement".
5.) In accordance with state regulations, in the event of f
6.) All Enviro-Flo lines to be laid level.
7.) Baffles to be installed in compartment tanks as shown
8.) A minimum of 6" of loam to used as a finish grade la
of deep rooted vegetation on or near leachbed, tank or sew
9.) Differential venting requires the high vent opening to
covered with a heavy wire mesh to prevent any foreign ob
10.) Garbarge Disposal systems may cause premature syst
11.) Maintenance should include pumping tank one every
12.) Install Myers ME3H pump (set on a 4" block) and i
for pump removal. Available at Water Industries Inc. Al
Auduble/Visual alarm to be installed in prominant locati
13.) Zabel filter to be cleaned and checked every 6 mont

GENERAL NOTES:

1.) The subsurface disposal system has been designed in
Control as of of date of issue of the "Approval for Const
those rules and regulations. Any changes or deviations f
componants the contractor must notify the state inspecto
place.
2.) This plan does not conform to local regulations. A va
3.) This is a site plan and NOT a formal survey. The des
delineation. Prior to installation a Licensed Land Survey

PUMP SPECIFICATIONS

DOSE VOLUME & SERV

Loading Volume =
Service Line Legnth =
Service Line Diameter =

TOTAL DYNAMIC HEAD

D-Box Elevation
Alarm on Elevation =
Pump on Elevation =
Pump Off Elevation
Bottom of Tank Elevation


PUMP CAPACITY (gpm):

Discharge Rate

Drill 3/8" hole in checkvalve flapper to ba

SEPTIC DESIGN: THIS PLAN SHOULD NOT BE USED TO DETERMINE BOUNDARIES, BEFORE LEACH FIELD IS INSTALLED IT IS RECOMMENDED THAT ALL BOUNDARIES

CROSS SECTION (NOT TO SCALE).



CONSTRUCTION NOTES :

1.) Septic Tank; Precast concrete, AASHTO rating of H-20 or better. Distributed by A.J Foss concrete of Farmington, NH.
Tank to be sealed and grouted watertight and pump chamber shall be vented with 2" vent pipe, opening shall be covered with a wire mesh to prevent any foreign objects from entering the pipe. Vent opening to be 3' above grade.
2.) D-Box ; 5 outlet Precast Concrete, Distributed by A.J Foss of Farmington, NH.
3.) Sewer pipe from building to septic tank shall be 4" solid SDR 26 (or equal) solvent welded plastic pipe with a minimum pitch of 1/4" (2 %) per foot. Pump discharge pipe shall be 1.5" Plastic 100 psi minimum pressure rated plastic pipe. Install elbow at end of sewer line where it enters tank 2 and the D-Box to reduce velocity of flow. Pump line to be installed below frost penetration (or insulated) and backfilled with clean sand free of stones. *Sewer line (1.5") from tank 1 to tank 2 should be laid at such a pitch to allow back flow within the line from tank 2 to tank 1.*
4.) All connections to be sealed with "waterplug cement".
5.) In accordance with state regulations, in the event of failure the system is to be built in place or in a suitable replacement site.
6.) All Enviro-Flo lines to be laid level.
7.) Baffles to be installed in compartment tanks as shown by A.J Foss concrete.
8.) A minimum of 6" of loam to used as a finish grade layer, planted with a perennial grass mix to prevent erosion. Do not plant or allow the growth of deep rooted vegetation on or near leachbed, tank or sewer line. Keep leachbed clear of heavy vegetation.
9.) Differential venting requires the high vent opening to be 10' above the lower, and should be supported by a 4X4 post. All vent openings to be covered with a heavy wire mesh to prevent any foreign objects from entering the pipes.
10.) Garbarge Disposal systems may cause premature system failure and are not recommended.
11.) Maintenance should include pumping tank one every six months and tank two Bi-annualy.
12.) Install Myers ME3H pump (set on a 4" block) and installed per manufacturers recommendations. Martinson Quick Disconnect model NGRD8 for pump removal. Available at Water Industries Inc. Alton, NH. Float alarm to be installed in pump chamber and set at elevations specified. Auduble/Visual alarm to be installed in prominant location in/on building. Seperate electronic circuits shall be provided for pump and alarm.
13.) Zabel filter to be cleaned and checked every 6 months when tank 1 is pumped or as needed for proper filtration of solids.

GENERAL NOTES:

1.) The subsurface disposal system has been designed in accordance with the rules, regulations and practices of the N.H Water Supply & Pollution Control as of of date of issue of the "Approval for Construction" (valid for 4 years). Construction must be done in strict accordance with this plan and those rules and regulations. Any changes or deviations from this plan may require revised or amended plans. Prior to backfilling or covering any componants the contractor must notify the state inspector for inspection of the system. In the event of system failure the system shall be repaired in place.
2.) This plan does not conform to local regulations. A variance was obtained through the planning board for installation as shown.
3.) This is a site plan and NOT a formal survey. The designer is not a licensed Land Surveyor and assumes no responsibility for boundary line delineation. Prior to installation a Licensed Land Surveyor should be consulted as to the location of boundary lines.

PUMP SPECIFICATIONS : Myers ME3H

DOSE VOLUME & SERVICE LINE SPEC'S:

Loading Volume = 750.0 gpd....
Service Line Legnth = 30.00 Feet
Service Line Diameter = 1.5 inches

-:- 8 doses minimum/day = 93.75
Actual number of Doses/day = 8
Pump Chamber gals/inch = 6.2 gpi
Pump Switch / Off to On = 15.0 inches
Actual Pump Dose = 93.0 gals

TOTAL DYNAMIC HEAD (TDH) 11.06 Feet

D-Box Elevation = 102.44 feet
Alarm on Elevation = 97.37'
Pump on Elevation = 96.87'
Pump Off Elevation = 95.62'
Bottom of Tank Elevation = 94.12 feet

Pump on Block, Block Height = 4.00 inch
Static Head = 6.82'
Delivery Loss = 4.24'
Total Dynamic Head (TDH) = 11.06'

PUMP CAPACITY (gpm): (w/DBL FLOAT SWITCH AND ALARM)


Discharge Rate = 30 gpm
Myers ME Delivers = 30 gpm
Pump Running Time = 3.1 mins

Drill 3/8" hole in checkvalve flapper to backdrain


O LIBRARY WELL

...ECOMMENDED THAT ALL BOUNDARIES BE LOCATED BY A PROFESSIONAL LAND SURVEYOR.

Property Overview



Location Map



Direction from Route 101: Take exit 2 (Hooksett Road) follow South 1.2 miles. Subject parcel is on the left, Village Children's Center of Auburn.

SOILS DATA TEST PIT #1

CANTON GRAVELLY FINE SANDY LOAM 3-8% SLOPE
ROCKINGHAM COUNTY SOIL SURVEY DATA : 42B

DEPTH	COLOR	TEXTURE	STRUCTURE	CONSISTENCE
0 - 14"	10YR 4/3	Loamy	Granular	Loose
14" - 25"	10YR 7/8	Loamy / Sand	Single Grain	Loose
25" - 40"	2.5Y 6/8	Loamy / Sand	Single Grain	Loose
40" - 56"	2.5Y 6/3	Sandy / Clay	Granular	Loose
56" - 108"	2.5Y 6/4	Clayey	Massive	Firm

Perc Test: 3 Min / inch

Estimated Seasonal High Water Table is at 54" Below Original Grade
Roots were observed to 36" Below Grade
No Ledge observed.

CALCULATIONS : SYSTEM CAPACITY 750 GPD

Required Spacing between Enviro-Flo pipes: 0-10% slope with a 1-10 min/in perc rate is 1.5' center to center.


Linear Footage Requirement: 750 GPD \ 100 * 47 = 352.5 Linear feet of Enviro-Flo pipe Based on information provided in the "

352 ft. / 10 ft. = 36 legnths of enviro-flo pipe required.

DESIGN INTENT

THE BED BOTTOM IS TO BE A MINIMUM OF 48" ABOVE THE ESTIMATED SEASONAL HIGH WATER TABLE (SHWT).

ME3H SERIES CURVE



Magnetic North 2003

SCALE : 1" = 20'

Prepared For :


Village Children's Center of Auburn
32 Hooksett Road
Auburn, N.H. 03032

NEW HAMPSHIRE Designer of Subsurface Disposal Systems PETER M. KASPRZYK No. 1082

Plan By :


Peter Kasprzyk
2344 Wakefield road
Wakefield, NH 03872

Scale 1" = 20'	Date	3-17-2004	Dwg No.	001-04





PLOT PLAN FOR 3 EATON HILL RD

PAT. Reynolds




Scale 1"=100'
Plan for
DAVID & KATHLEEN HOLMAN
Chester Road, Auburn N.H.
Lot #1
Lot #2
Septic System
well
Griffin Library
Chester Road
EATON ROAD
S 65°37'E
N 25°23'E
110.00'
Lot #1
106
104
102
S 80-15E
S 64°37'E
150.0
Type "B"
Test Pit 4-30-76
Distribution Box
750 Gal Septic Tank
2 Bdrm house
30'
Perk Test 4-30-76
Type "A"
well
Bench 3 stake 100.0
N 15° 30'E
285.68
CHESTER ROAD
C.B
Brook 100.4
Griffin Library
S 14°30'E
CROSS SECTION OF DISPOSAL SYSTEM
NO SCALE
FINISH GRADE 101.0
100.5
100.2
100.0
99.7
30'
REMOVE TOP SOIL BEFORE PLACING FILL.
FILL MATERIAL TO BE SAME AS ORIGINAL TOP SOIL.
TYPE "A" - SOLID LINES ———, PITCH, 1/4" = 1.0 MIN.
C-1 PIPE LAID WITH TIGHT JOINTS.
TYPE "B" BROKEN LINES - - - -, PITCH, LEVEL.
4" DISTRIBUTION PIPE LAID WITH TIGHT JOINTS.
-NOTE-
ORANGEBURG, PERFORATED, OR PLASTIC PIPE (P.V.C) MAY BE USED.
NO FOUNDATION DRAINS.
END SECTION
NO SCALE
ORIGINAL GROUND
2"
6"
2.5'
UNIFORMLY GRADED WASHED GRAVEL, ONE SIZE, OF YOUR CHOICE 3/4" TO 2 1/2". SEPERATE FROM BACKFILL WITH STRAW, BLDG. PAPER, ETC.
TEST PIT
101.0
6" loam
PERK TEST 99.0
9 1/2' Sand & small stones
10'
91.0
PERK TEST 11.0 min/in
SEASONAL WATER TABLE 7.0
HIGHWATER TABLE 6.0
NO LEDGE to 10'
SOIL CLASSIFICATION GB
sheet 23
SHEET 23
1 1/2 MI. ± RES 101
CHESTER RD.
EATON RD.
EDGE OF MAP
Scale 1:20,000
Sewerage Disposal System
-FOR-
Lawrence & Helen Hurley
CHESTER ROAD - Route 121
Auburn N.H.
SCALE: 1"=20'
July 1976
BK.140 PG.49
D.G.C.
WALTER F.
293 YOUNG STREET
MANCHESTER, N.H. 03103
RECEIVED
JUL 20 1976
WATER SUPPLY & POLLUTION CONTROL COMMISSION


EATON ROAD
S 65°-37'E 314.85'
102.5
102.7
Lot#1
N 25°23' E
110.00'
S 88-15E 275.79
106
104
102
well
septic system
Type "B"
Test Pit 4-30-76
Distribution Box
750 Gal Septic Tank
2 Bdm house
30'
perk Test 4-30-76
Type "B"
S 64-37'E 150.0
Bench 3' stake 1000
2.00
N 15° 30' E
285.68
well
150
C.B.
Brook 100'
CHESTER ROAD



Scale 1"=100'
...n for
...& KATHLEEN HOLMAN
...r Road, Auburn N.H.
Lot #2
Septic System
Existing House
Griffin Library
o well
Chester Road
100.5
100.2
100.0
99.7
FINISH GRADE 101.0
99.0
30'
CROSS SECTION OF
DISPOSAL SYSTEM
NO SCALE
REMOVE TOP SOIL BEFORE PLACING FILL.
FILL MATERIAL TO BE SAME AS ORIGINAL
TOP SOIL.
TYPE "A" - SOLID LINES ———, PITCH, 1/4" = 1.0 MIN.
C-I PIPE LAID WITH TIGHT JOINTS.
TYPE "B" BROKEN LINES - - - - -, PITCH, LEVEL.
4" DISTRIBUTION PIPE LAID WITH TIGHT JOINTS.
-NOTE-
ORANGEBURG, PERFORATED, OR PLASTIC PIPE (P.V.C)
MAY BE USED.
NO FOUNDATION DRAINS.
END SECTION
NO SCALE
ORIGINAL GROUND
2"
6"
2.5'
UNIFORMLY GRADED WASHED GRAVEL, ONE SIZE, OF YOUR CHOICE
3/4" TO 2 1/2". SEPERATE FROM BACKFILL WITH STRAW, BLDG. PAPER, ETC.
TEST PIT
101.0
6" loam
9 1/2' sand & small stones
10'
PERK TEST 99.0
91.0
PERK TEST 11.0 min/in
SEASONAL WATER TABLE 7.0
HIGHWATER TABLE 6.0
NO LEDGE to 10'
SOIL CLASSIFICATION GB
Griffin Library
25.68
sheet 23
SHEET 23
EATON RD.
RAYMON RD.
1 1/2 MI. to RTE. 101
CHESTER RD.
LOCUS
EDGE OF MAP
Scale 1:20,000
Sewerage Disposal System
-FOR-
Lawrence & Helen Hurley
CHESTER ROAD - Route 126
Auburn N.H.
SCALE: 1"=20'
July 1976
BK. 140 PG. 49
D.G.C.
WALTER F.
293 YOUNG STREET
MANCHESTER, N.H. 03103
RECEIVED
JUL 20 1976
WATER SUPPLY & POLLUTION CONTROL COMMISSION

'76 DEC -7 PM 2:05
REC'D ROCKINGHAM COUNTY
REGISTRY OF DEEDS



C-6484

1" = ____

...DIVISION PURSUANT TO THIS TITLE AND THAT THE LINES OF STREETS AND WAYS SHOWN ARE THOSE OF PUBLIC OR PRIVATE STREETS OR WAYS ALREADY ESTABLISHED AND THAT NO NEW WAYS ARE SHOWN.


Anne W Bialobrzeski 8/9/04

ANNE W. BIALOBRZESKI LLS #752 DATE


STATE OF NEW HAMPSHIRE No. 752 ANNE W. BIALOBRZESKI LICENSED LAND SURVEYOR


Anne W Bialobrzeski

8/9/04



To P Board — we were to get septic design approved & go back — 100' waiver granted for well radius


CHESTER ROAD
N 15°-30'E
85.68'
200.0
Septic System
Well
N 74°-30'-33" 150.00'
150.00' S 64°-37'E
DAVID & PATRICIA REYNOLDS
N 25°-23'E 110.00'
LOT #1 2.0A±
N 88 27
314.85' S 65°-37'E
EATON ROAD
50.0'
150.22 S 49°-27 W
218.59' S 13°-15'E
WINIFRED TUSON HEIRS
2472-568
APPROVED
AUBURN, N. H. PLANNING BOARD
CHAIRMAN
DATE Nov. 10 1976
10692
PLAN of LAND for
DAVID AND KATHLEEN HOLMAN
CHESTER ROAD
AUBURN, N.H.
SCALE 1"=40'
JULY 1976
Book 140 Pg 49
WALTER F. O'NEILL C.E.
293 YOUNG ST.
MANCHESTER N.H.



Reference :

Auburn Tax Map 26 Lot 10-1

Plan of Land for

David & Kathleen Holman
Chester Road
Auburn, NH

by Walter F O'Neil
293 Young Road
Manchester, NH 03103

Sewage Disposal Design
Approval #56406 Sub Approval #10692
for Lawrence & Helen Hurley
Chester Road Rte 121
Auburn,NH


by Walter F O'Neil
Manchester, NH 03103

Notes:

Current Septic system has a 1000 Gallon tank with a conventional leach bed.

Approval # NHDES 56406

Rockingham Soil Service: 42B
Canton Fine Sandy Loam



Village Childrens Center of Auburn
32 Hooksett Road
Auburn, NH 03032

Date : June 23, 2003

D14247
C6484
C14627
D27977
2247-1094
2433-0334
2472-0568
2947-1363
2612-2349
3765-2137
2886-2656